



Sibiu-Pitesti motorway, section 1, Sibiu-Boița

Data and facts

| | |
|-----------|--|
| Company | S.C. PORR Construct S.R.L. |
| Type | Road construction |
| Runtime | 04.2019 - 05.2023 |
| Principal | National Company for the Administration of Road Infrastructure |

[Project report online](#)

www.porr-group.com



Securing connectivity.

| Road works. | | Bridge works, total length: 2,094.25m. | |
|--------------------|-------------|--|-----------|
| Excavation | 1,912,877m³ | Drilled piles | 15,086m |
| Fill | 1,330,932m³ | Concrete | 88,624m³ |
| Subgrade layer | 216,423m³ | Reinforcement | 11,977t |
| Ballast | 162,140m³ | Prefabricated beams | 393pcs. |
| Stabilized ballast | 66,943m³ | Formwork | 122,082m² |
| Asphalt mixture | 209,389t | | |

Impressions



Image notes

1 PORR RO SP1 01

Do you have questions about the project or would you like to learn more? Feel free to contact us for further information.

PORR AG Group Communications

Absberggasse 47

1100 Wien

T +43 50 626-0

E-Mail: comms@porr-group.com