



Sibiu-Boița

Sibiu-Pitesti motorway, section 1

Data and facts

Company	PORR Construct S.R.L.
Type	Road construction
Runtime	04.2019 - 05.2023
Principal	National Company for the Administration of Road Infrastructure

[Project report online](#)

www.porr-group.com



Securing connectivity

At the beginning of this project, the according Sibiu-Pitești Motorway sector was divided into five sections. For Section 1, with a length of 13.170km, the motorway route starts in the area of Șelimbăr, at the junction with Sibiu Bypass. The motorway route crosses the localities of Șelimbăr and Tălmăciu to the southwest of the DN7 up to the Boița area. There a road junction is to be built, ensuring the connectivity of Sibiu-Pitești Motorway with the DN7 for the future.

Main activities

- Motorway with two lanes in each direction, hard surface width of 26m along the length of 13.170km
- Two road junctions: Sibiu and Boița
- Two service spaces of type S1 at km 8.200 left, km 8.200 right
- A maintenance and coordination centre in the area of the Boița road junction
- A viaduct with 10 spans at km 10.470, at a length of 414.70m
- A viaduct with 8 spans at km 12.375, at a length of 651.40m
- 27 bridges and passages
- 27 culverts

Road works		Bridge works, total length: 2,094.25m	
Excavation	1,912,877m ³	Drilled piles	15,086m
Fill	1.330,932m ³	Concrete	88,624m ³
Subgrade layer	216,423m ³	Reinforcement	11,977t
Ballast	162,140m ³	Prefabricated beams	393pcs.
Stabilized ballast	66,943m ³	Formwork	122,082m ²
Asphalt mixture	209,389t		

Impressions



Image notes

1 Sibiu-Pitesti

Do you have questions about the project or would you like to learn more? Feel free to contact us for further information.

PORR AG Group Communications

Absberggasse 47

1100 Wien

T +43 50 626-0

E-Mail: comms@porr-group.com